

KANSAS

STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION
RECEIVED
JUN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling Co.
Complete Address Box 18407, Wichita, Kansas
Lease Name Hastings Well No. 1
Location NE SW Sec. 9 Twp. 22 Rge. 21 ~~(E)~~ (W)
County Hodgeman Total Depth 4365'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Globe Cementing Pump
Address Great Bend, Kansas License No. _____
Operation Completed: Hour 1:30PM Day 12 Month 6 Year 1972

The above well was plugged as follows:

8 5/8" to 364' circulated w/ cement. 5 1/2" to 4358' circulated w/, cement.
No perforations- open hole 4358' to 4365'. Plug bottom w/ 20 sacks cement.
Top of cement 4100' Mud 4100' to 700'
Spotted 15 sacks cement 700' to 600' Mud 600' to 40'
Plug & 5 sacks cement 40' to 0'. Globe cementing Pump Truck
No Pipe Pulled.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging Supervisor

INVOICED

DATE 6-14-72
INV. NO. 5875-W