

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Take All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217


Locate well correctly on above  
Section Plat

Pawnee County, Sec. 30, Twp. 22S, Rge. 20W (E) (W)  
 Location as "NE/CNWSW2" or footage from lines NW NW SE  
 Lease Owner Voyager Pets, Inc; Ks-Neb Nat Gas & Sterling Drilling Co.  
 Lease Name Lynam Well No. 1  
 Office Address P. O. Box 129, Sterling, Kansas 67579  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed February 8, 1975 10  
 Application for plugging filed February 7, 1975 10  
 Application for plugging approved February 7, 1975 19  
 Plugging commenced 8:00 AM, February 8, 1975 10  
 Plugging completed 9:30 AM, February 8, 1975 10  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 10  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4530' Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud, to surface.  
Halliburton pumped 120 sacks 50/50  
Pozmix through 8 5/8" swage in surface  
pipe and shut in.

*Recd  
2-18-75*

Name of Plugging Contractor Sterling Drilling Company  
 Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
 (Address)

Subscribed and Sworn to before me this 13th day of February, 1975

Bernard Laudermilk  
 Bernard Laudermilk, Notary Public.

My commission expires  
**BERNARD LAUDERMILK—NOTARY PUBLIC**  
 My Commission Expires Jan. 22, 1978

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- LYHAM #1

Located: NW NW SE, Section 30-22S-20W, Pawnee County,  
Kansas

OWNER: Voyager Petroleum, Inc.; Kansas-Nebraska Natural Gas Company,  
Inc. and Sterling Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 29, 1975

COMPLETED: February 8, 1975

TOTAL DEPTH: 4530'

LOG

CASING RECORD

0 -	30	Surface Soil and Clay
30 -	70	Sand
70 -	240	Shale and Clay
240 -	340	Shale
340 -	687	Shale, Red Bed, Sand
687 -	704	Blane Section
704 -	1235	Shale, Red Bed, Sand
1235 -	1355	Shale, Sand
1355 -	1425	Lime and Shale
1425 -	1845	Shale and Shells
1845 -	2315	Shale
2315 -	2740	Lime and Shale
2740 -	2870	Lime
2870 -	3335	Lime and Shale
3335 -	3470	Lime, Chert
3470 -	3650	Lime, Chert, Shale
3650 -	3712	Lime and Shale
3712 -	3800	Shale
3800 -	4359	Lime
4359 -	4415	Lime and Shale
4415 -	4470	Lime
4470 -	4497	Lime, Shale, Chert
4497 -	4530	Chert, Lime

Ran 6 joints 8 5/8" casing, 249.36' set  
at 262' F.B. with 250 sacks Pozmix 60/40,  
3% cc. Plug down at 6:15 PM, 1-29-75.

Plugged.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1975  
CONSERVATION DIVISION  
Wichita, Kansas