


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Hodgeman County, Sec. 24 Twp. 22S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Bradshaw Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 23 1959
Application for plugging filed November 23 1959
Application for plugging approved November 23 1959
Plugging commenced November 23 1959
Plugging completed November 23 1959
Reason for abandonment of well or producing formation No commercial quantities of oil found.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4716 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Bottom plug at 550 feet with 20 sacks of cement; Set second plug at 200 feet with 20 sacks of cement; Set top plug at 35 feet with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1960
CONSERVATION DIVISION
Wichita, Kansas
1-19-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor IMPERIAL OIL OF KANSAS, INC.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
R. L. Bacon (employee of ~~owner~~ or ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God IMPERIAL OIL OF KANSAS, INC.
(Signature) By: [Signature] V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 60

My commission expires July 7, 1962 [Signature] Notary Public.

DRILLER'S LOG

RECEIVED
STATE GEOLOGICAL SURVEY
CONSERVATION COMMISSION

JAN 19 1960

CONSERVATION DIVISION
Wichita, Kansas

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Bradshaw No. 1
C SE NE Sec. 24-22S-24W
Hodgeman County, Kansas

Total Depth: 4716'

Commenced: 11-8-59 Completed: 11-23-59

Elevation: 2401' K.B.
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 215' with 175 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Clay & Sand	150'		
Sand & Shale	215'	Heebner	3786' (-1385)
Shale - Shells & Sand	1150'	Toronto	4003' (-1602)
Sand & Shale	1663'	Brown Lime	4056' (-1655)
Anhydrite	1692'	Lansing	4064' (-1663)
Shale & Shells	2510'	Base Kansas City	4395' (-1994)
Shale & Lime	3745'	Cherokee shale	4588' (-2187)
Lime	4698'	Mississippi Chert	4694' (-2293)
Lime & Chert	4716'	Rotary Total Depth	4716' (-2315)
Total Depth	4716'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: R.L. Bacon
R.L. Bacon - Vice-President

Subscribed and sworn to before me this 18th day of January, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier - Notary Public