

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Hodgeman

County. Sec. 24 Twp. 22 Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines S/SE/SW

Lease Owner Great Bend Pipe & Supply Company

Lease Name Springer Well No. "A" #2

Office Address West 10th, Box 414, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed Yes 19____

Application for plugging approved Yes 19____

Plugging commenced 2-5 1959

Plugging completed 2-13 1959

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Hives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4663' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				4 1/2"		2,582'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 4663'.

Plugging started 2-5-59. Finished 2-13-59.

Plugged off bottom and sanded back to 4600'. Dumped 4 sacks cement.

Worked and shot pipe. Shot 4 1/2" casing at 2,582'. Circulated and

spotted 45 bbls oil. Mixed and circulated 35 sacks mud. Pulled pipe

out of hole and plugged well as follows: Mudded to 550'. Set rock

bridge and dumped 20 sacks cement. Filled hole with mud to 35'.

Set rock bridge and mixed 10 sacks cement for cap on well.

Well completed.

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1959

WISIC

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February, 1959

My commission expires November 8, 1960.
Betty G. Edman Notary Public.

PLUGGING
FILE SEC. 24 T22 R. 24 W
BOOK PAGE 14 LINE 20

SHELL OIL COMPANY
SPRINGER "A" # 2

15-083-10317-0000

SE SW Sec. 24-22S-24W
HODGEMAN COUNTY, KANSAS

Total Depth: 4663'
Comm: 10- 9-50
Comp: 11- 5-50

~~BYE~~
~~LB~~
F

Y13

Casing

8 5/8" Set @ 821'
4 3/4" Set @ 4660'

B & R Drilling Co., Contractor

Cement

500 sacks of Bulk
150 sacks of Bulk

Formation	Depth:
Surface Clay	40
Shale	100
Shale-Shells	310
Sand-Shale-Pt. Iron	385
Shale-Shells	700
Sand-Shale	775
Red Bed-Shall	821
Red Bed-Shale	1025
Lime	1055
Red Bed	1130
Sand	1460
Red Bed-Shale	1750
Red Bed-Lime	1850
Shale-Shells	2090
Salt-Shale	2235
Red Bed-Shale	2390
Lime-Shale	2540
Anhydrite	2580
Lime-Shale	3975
Lime	4035
Lime-Shale	4075
Lime	4395
Lime-Shale	4609
Lime	4622
Lime-Chert	4629
Chert	4637
Lime	4663'

4660
900

3760

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Violet Keller

Subscribed and sworn to before me this 15th day of November, 1950.

Clara Linnell
Notary Public

My commission expires: 6-17-54

PLUGGING			
FILE	SEC. 24	T. 22	R. 24W
BOOK	PAGE 14	LINE 20	

40 to 45 more than the other side
2 miles or 3 miles left side
of road. No turn

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1959
CONSERVATION DIVISION
Wichita, Kansas

BOOK	NO	1st	100
SERIAL	100	1st	100
STANDARD			

[Handwritten signature]

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS