

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

HODGEMAN

County. Sec. 27 Twp. 22 Rge. 24 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE, SE, NE

Lease Owner MULL DRILLING COMPANY

Lease Name TARMAN Well No. 1

Office Address 670 FOURTH NATIONAL BLDG, WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY ROTARY

Date well completed 8-31 1958

Application for plugging filed 8-31 1958

Application for plugging approved 8-31 1958

Plugging commenced 8-31 1958

Plugging completed 8-31 1958

Reason for abandonment of well or producing formation No productible zone

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MERLE A. RIVES

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4680' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	419' W	250 sax.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud up to 415', pushed wooden plug to 415', capped with 20 sx. cement through drill pipe.  
Heavy mud to 35', pushed wooden plug to 35', capped with 10 sx. cement to base of well cellar.  
Job complete @ 10:30 PM, 8-31-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON ss.  
VERNE A. MORRIS (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris  
Route #2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 1958

My commission expires November 12, 1958

*Beaufort*  
**RECEIVED**  
STATE CORPORATION COMMISSION  
Notary Public.

**PLUGGING**  
FILE SEC. 27 T. 22 R. 24  
BOOK PAGE 128 LINE 1

SEP 19 1958 9-19-58

W L L LOG

15-083-00114-0000

COMPANY MULL DRILLING COMPANY

SEC. 27 T. 22S R. 24W

FARM TARMAN NO. 1


LOC. NE, SE, NE

TOTAL DEPTH 4680'

COUNTY HODGEMAN CO., KANSAS

COMM. August 12, 1958 COMP. August 31, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 3/8" @ 419' W/250 max.

ELEVATION 2400' BP

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS:

165	Shab & rock
290	Yellow clay & shale
419	Blue shale
1010	Shale
1045	Anhydrite
2425	Shale & shells
2585	Shale
2900	Lime & shale
2952	Lime
3565	Lime & shale
3707	Shale & lime
4218	Lime & shale
4292	Lime
4452	Lime & shale
4680	Lime
4680	T. D.

State of KANSAS }  
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 TARMAN well

*Verne A. Morris*

Subscribed and sworn to before me this 17th day of September 19 58

My Commission Expires: November 12, 1958

*[Signature]*  
NOTARY PUBLIC