

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 25 Twp. 30S Rge. 9W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines


C SE NE
Lease Owner Graves Drilling Co., Inc.
Lease Name Swingle Well No. 3
Office Address 910 Union Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed April 14 1978
Application for plugging filed April 14 1978
Application for plugging approved April 14 1978
Plugging commenced April 14 1978
Plugging completed April 14 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4390
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240 feet. Pumped 40 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well collar. Plugged rat hole with 3 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1978

(If additional description is necessary use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1978

My commission expires May 9, 1979

Betty Brandt
Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: April 7, 1978

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: April 14, 1978

CASING RECORD: 5 Jts. 220' 8 5/8" used
cemented with 225 sacks

LOCATION Swingle No. 3
C SE NE
Section 25-30S-9W

0 - 220 Sand- & Red Bed
 220 - 277 Red Bed
 277 - 1055 Red Bed & Shale
 1055 - 3091 Shale & Lime
 3091 - 3323 Shale
 3323 - 3715 Shale & Lime
 3715 - 4025 Lime & Shale
 4025 - 4138 Lime
 4138 - 4340 Lime & Shale
 4340 - 4390 Lime & Chert
 4390 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 APR 24 1978
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 20th day of April, 1978

Betty Brandt
Betty Brandt Notary Public

My commission expires:

May 9, 1979

