

WELL PLUGGING RECORD  
K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

RECEIVED  
AUG 21 2002  
8-21-02  
KCC WICHITA  
TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

15-095-30008-00-00  
spud 10-24-64

API NUMBER \_\_\_\_\_  
LEASE NAME Holcomb E  
WELL NUMBER 1  
330 ft. from S Section Line  
990 ft. from E Section Line  
SEC. 26 TWP. 30 RGE. 9 (E) or (W)  
COUNTY Kingman  
Date Well Completed \_\_\_\_\_  
Plugging Commenced 8/2/02  
Plugging Completed 8/6/02

LEASE OPERATOR Messenger Petroleum, Inc.  
ADDRESS 525 S. Main, Kingman, KS 67068  
PHONE # (620 ) 532-5400 OPERATORS LICENSE NO. 4706

Character of well gas  
(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 8/2/02 (date)  
by Doug Louis (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4380  
Show depth and thickness of all water, oil and gas formations  
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	219	none
				4 1/2	4377	1040

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Sand at 4260, bailed 4 sacks cement. Pipe parted 1040, pumped plug, 50 sacks cement. Pull to 900 and pump 35 sacks cement. Pull to 270, circulated cement to surface with 115 sacks. Lay down rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Messenger Petroleum, Inc.  
STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me 19 day of August 2002

My commission Expires: 9/9/2002



OR