

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21,387-0000

LEASE NAME Cornelius

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 29 TWP. 30S RGE. 9 or

COUNTY Kingman

Date Well Completed 12-5-83

Plugging Commenced 11-7-94

Plugging Completed 11-7-94

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE#(316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4370' Bottom 4385' T.O. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	255'	8-5/8"	255'	None
		0	4448'	5-1/2"	4448'	2480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set
Plugged and abandon using 60/40 Pozmix, 4% gel. Set 1st plug @ 1500' w/35 sks; 2nd plug @ 1050' w/35 sks. 3rd plug @ 316 w/90 sx and circulate to surface. Top off with 25 sacks. Plugging complete 11-7-94

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P. O. Box 781624, Wichita, KS 67278-1624

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3017 N. Cypress, Wichita, KS 67226-4003

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1994

DEBORAH ANN PAULUS
NOTARY PUBLIC
STATE OF KANSAS
My Commission Expires January 1, 1996

Deborah Ann Paulus
Notary Public