

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 29 Twp. 30S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines SW 1/4 NW 1/4 SE 1/4

Lease Owner Champlin Oil & Refining Co.

Lease Name Cornelius Well No. 1

Office Address Box 167, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed July 19, 19 56

Application for plugging filed June 17, 19 59

Application for plugging approved June 22, 19 59


Plugging commenced June 19, 19 59

Plugging completed June 23, 19 59

Reason for abandonment of well or producing formation Non-Productive

If a producing well is abandoned, date of last production 1-17 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4422' Feet

Show depth and thickness of all water, oil and gas formations. 4358' PBTD

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4" OD	231'	None
				5 1/2" OD	4422'	3345'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 4358' PBTD to 4300' and ran 5 sacks of cement from 4300' to 4270', then filled hole with mud from 4270' to 210' and set rock bridge from 210' to 200' and ran 25 sacks of cement filling hole to 150' then filled hole with mud from 150' to 30' and ran 15 sacks of cement filling hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1959 6-26-59

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co. License #396

Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. W. Meyers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P.O. Box 167, Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of June, 19 59

My commission expires 5-22-62

Notary Public.

PLUGGING
FILE SEC. 29T 30R 9W
BOOK PAGE 46 LINE 28

FORMATION RECORD

CHAMPLIN OIL & REFINING CO.
 Ray Cornelius #1
 SW NW SE Sec. 29-30S-9W
 Kingman County, Kansas


Surface clay	0	25
Sand	25	45
Shale shells	45	980
Anhydrite	980	1010
Shale shells, red bed	1010	1250
Shale shells	1250	1435
Lime, shale	1435	2295
Shale, shells	2295	2515
Shale, lime	2515	3050
Lime	3050	3100
Lime, shale	3100	3680
Lime	3680	4175
Shale, lime	4175	4220
Lime	4220	4315
Shale, lime	4315	4364
Lime	4364	4422
Total depth	4422	

J. W. Meyers

J. W. Meyers, Dist. Supt.

Subscribed and sworn to before me this 17th day of June, 1959.
 My commission expires 5-22-62.

N. Bennett Stearns



RECEIVED
 STATE CURATOR'S COMMISSION

JUN 18 1959

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 29 T. 30 R. 9 W
 BOOK PAGE 46 LINE 28