

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

API NUMBER 1956
LEASE NAME Graham
WELL NUMBER 1
330 ft. from S Section Line
2310 ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

SEC. 29 TWP. 30 RGE. 9 (E) or (W)
COUNTY Kingman

LEASE OPERATOR R & B Oil & Gas, Inc.
ADDRESS PO Box 195, Attica, KS 67009
PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191

Date Well Completed 1956?
Plugging Commenced 2/20/02
Plugging Completed 2/22/02

Character of well ~~Oil~~ Gas
(Oil, Gas, D&A, SWD, input, Water Supply Well)

RECEIVED
APR 17 2002

The plugging proposal was approved on 2/20/02 (date)
by Doug Louis (KCC District Agent's Name)

KCC WICHITA

Is ACO-1 filed? ~~Yes~~ No if not, Is well log attached? not available to us

Producing Formation Mississippi Depth to Top 4338 Bottom 4443 T.D. 4445
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Gas	4338	4443	8 5/8	196	none
				4 1/2	4443	1808

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Sand at 4297, baled 4 sks cem. shot pipe at 2842, 1808, came free. Pull to 1350, pump 35 sacks cement. Pulled to 900, pumped 35 sks cem. Pull to 250, circulate cem. to surface w/5 sks cem. Pull rest of pipe. Check, cem. at 120, pump 50 sks to fill.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Randy Newberry
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 5th day of April, 2002

Rebecca S. Newberry Notary Public

My commission Expires: 7-21-2005

Form CP-4 Revised 05-88



PK