

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 33 Twp. 30 Rge. 9 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

NW SE NE  
Lease Owner The Maurice L. Brown Company  
Lease Name Westerman Well No. 1

Office Address Suite 200, Sutton Place Building, Wichita, KS.  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed January 7 1978  
Application for plugging filed January 7 1978  
Application for plugging approved January 7 1978  
Plugging commenced January 7 1978  
Plugging completed January 7 1978

Reason for abandonment of well or producing formation  
Abandonment of well

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 4440'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		Surface	263'	8 5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
1st plug cement @ 270' w/35 sx.  
2nd plug cement @ 40' w/12 sx.  
Bridge Rathole w/3 sx.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 03 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Vern Haselhorst (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.


(Signature) Vern Haselhorst

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1978

Appointment  
My commission expires July 29, 1981

Marjorie P. Jennings  
Notary Public.



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Westerman #1  
NW-SE-NE Sec 33-30S-9W  
Kingman County Kansas

Commenced: 12-27-77

Completed: 1-7-78

OPERATOR: MAURICE L. BROWN

Depth		Formation	Remarks
From	to		
0	75	Sand	Ran 75 jts of 8 5/8" csg
75	800	Redbed	set @ 263' Cemented w/
800	1130	Shale	225 sks Class A-3% CC
1130	1580	Shale-Lime-Shells	PD @ 5:15 p.m. 12-27-77
1580	1755	Shale-Lime	
1755	2070	Lime	
2070	2290	Lime-Shale	
2290	2525	Shale-Lime	
2525	3345	Lime-Shale	
3345	3600	Lime	
3600	3655	Sand	STATE CO
3655	4440	Lime	

MAR 03 1978

DRY & ABANDONED

STATE OF KANSAS )  
) SS  
COUNTY OF SEDGWICK)

CONSERVATION  
Wichita, Kansas

I, the undersigned, being duly sworn on oath, state that the above  
Drillers' Well Log is true and correct to the best of my knowledge and belief and  
according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
JAMES S. S. SUTTON II

Subscribed and sworn to before me this 19th day of January, 1978.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

