

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-01,315-000

LEASE NAME Swingle "N"

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 34 TWP. 30S RGE. 9 or (W)

COUNTY Kingman

Date Well Completed 9-4-83

Plugging Commenced 3-19-90

Plugging Completed 3-20-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE#(316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well lo. attached? _____

Producing Formation Mississippian Depth to Top 4368 Bottom T.D. 4440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	236	None
				5-1/2"	4438	3400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Set CIBP @ 4350'. Place 3-1/2 sx cement on top of plug w/dump bailer. Cut off 5-1/2" casing @ 3400'. Plug using 60-40 Pozmix, 6% gel using Halliburton pump truck as follows. Circulate hole. Bottom of 1st plug @ 1499 w/25 sx. Bottom of 2nd plug @ 1096' w/25 sx. Bottom of top plug @ 293' circulate to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 90



Deborah Ann Paulus
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1990

7-16-90
CONSERVATION DIVISION
Wichita, Kansas