


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Kingman County, Sec. 3' Twp. 30 Rge. 10W E 4N  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
SW SE SE

Lease Owner Texas Oil & Gas Corp.  
Lease Name Hudson 'A' Well No. 1  
Office Address 200 Douglas, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date Well completed 9/14/80 19  
Application for plugging filed 9/14/80 19  
Application for plugging approved 9/14/80 19  
Plugging commenced 9/14/80 19  
Plugging completed 9 p.m. 9/14/80 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations. TD 3235'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	252	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 240' with 40 sacks  
2nd plug @ 40' with 10 sacks  
10 sacks in rathole  
Job complete @ 9 p.m. 9/14/80

10-2-80

RECEIVED  
STATE CORPORATION COMMISSION

OCT - 2 1980

(If additional description is necessary, use BACK of this form)  
Name of Plugging Contractor Slawson Drilling Company, Inc. Conservation Division  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg - Slawson Drilling Co., Inc. (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
280 Douglas Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of September 1980

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Texas Oil & Gas Corp.  
 200 West Douglas  
 Wichita, Kansas 67202

WELL NAME: Hudson 'A' #1  
 SW SE SE Sec. 3-30S-10W  
 Kingman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 9/6/80

COMPLETED: 9/14/80

RTD: 3235'

SURFACE CASING: 8-5/8" set at 252' with 250 sx cement

0' to 263' Red Bed (12 1/4" Surface Hole)  
 263' to 814' Red Bed  
 814' to 1481' Red Bed & Lime & Shale  
 1481' to 1678' Shale  
 1678' to 2125' Lime & Shale  
 2125' to 2370' Shale  
 2370' to 2744' Lime & Shale  
 2744' (Howard)  
 2744' to 3235' Lime & Shale  
 RTD 3235'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Hudson 'A' #1 log for Texas Oil & Gas Corp.

RECEIVED  
 STATE CORPORATION COMMISSION

OCT - 2 1980

CONSERVATION DIVISION  
 Wichita, Kansas

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me this  
 30th day of September, 1980

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

