

*SL*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Midwestern Supply Co., Inc.

Complete Address 710 Union National Bldg., Wichita, Kansas

Lease Name Nichols Well No. 1-G

Location C NE SW Sec. 25 Twp. 22 Rge. 21 (E) (W)

County Hodgeman Total Depth 4541'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Russ Casinf Pulling.

Address Great Bend, Kansas License No. 623

Operation Completed: Hour 2:00PM Day 7 Month 7 Year 1970

The above well was plugged as follows:

8 5/8" to 401' circulated w/ cement. 4 1/2" to 4541' cemented.

Top perforations 4510' Plug bottom w/ sand & 4 sacks cement.

Top of cement 4350' Mud 4350' to 600'

Spotted 80 sacks cement 600' to 300' Mud 300' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Allied Pump Truck

Pulled 26 26' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Lewis  
Well Plugging Supervisor

DATE 7/10/70

INV. NO. 2200-U