

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corporation

Complete Address Bpx 1070, Great Bend, Kansas

Lease Name Salmans Well No. 1

Location C SW SE Sec. 5 Twp. 22 Rge. 22 ~~(E)~~ (W)

County Hodgeman Total Depth 4610'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Forbes Casing Pulling

Address Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 26 Month 10 Year 1970

The above well was plugged as follows:

8 5/8" to 248' circulated w/ cement. 5 1/2" to 4609' cemented,

Top perforations 44523' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4450' Mud 4450' to 850'

Spotted 80 sacks cement 850' to 550'. Mud 550' to 240'

Spotted 30 sacks cement 240' to 140' Mud 140' to 40'

Plug. Halls & 10 sacks cement 40' to 0'. Company Pump

Pulled 3340' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves  
Well Plugging Supervisor

DATE 10-30-70

INV. NO. 2783-W