

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-055-20,043-0001 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)
WELL OWNER/OPERATOR TEXACO E&P, INC. OPERATOR'S LICENSE NO. 4742
ADDRESS P. O. BOX 2700, PAMPA, TEXAS 79066-2700 PHONE # (806) 665-1876
LEASE (FARM) GARDEN CITY "B" WELL NO. 6 WELL LOCATION C-SE-SE COUNTY FINNEY
SEC. 5 TWP. 22S RGE. 33 (~~E~~ or W) TOTAL DEPTH 4,800' PLUG BACK TO 4,579'
*CIBP w/2 SACKS CEMENT SET
1-25-93
Check One:

OIL WELL XX GAS WELL D & A SWD or INJ WELL DOCKET NO.
SURFACE CASING SIZE 9-5/8" SET AT 449' CEMENTED WITH 315 SACKS
DV TOOL @ 2,782' CEMENTED WITH 100 SACKS
CASING SIZE 7" SET AT 4,799' CEMENTED WITH 125 SACKS
PERFORATED AT 4,638-44', 4714-22', 4738-44'
CONDITION OF WELL: GOOD XXX POOR CASING LEAK JUNK IN HOLE
PROPOSED METHOD OF PLUGGING SEE BACK

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10-25-93 8:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. M. BARNUM PHONE # (806) 669-8450
ADDRESS P. O. BOX 2700, PAMPA, TEXAS 79066-2700

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES LICENSE NO. 5287

ADDRESS P. O. BOX 1598, LIBERAL, KS 67905-1598 PHONE # (800) 853-3555

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED:

J. M. Barnum
(Operator or Agent)

OCT 20 1993

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

**GARDEN CITY "B" #6
C/SE/SE
SEC. 5-22S-33W
FINNEY COUNTY, KANSAS**

ABANDONMENT PROCEDURE

1. MIRU Service Unit.
2. TIH W/Tubing to 4579' - PBDT (CIBP @ 4588' W/2 sx cmt set 1-25-93).
3. Displace wellbore W/9# mud (180 BBLS).
4. POH W/Tubing.
5. Perforate 7" Csg. W/4 Way shot @ 1100'.
6. Establish circulation in 9-5/8" & 7" annulus and circulate cement to surface (170 sx 60/40 Pozmix w/8% gel).
7. Leave 7" casing full of cement to surface (150 sx).
8. Cut off 9-5/8" surface casing at 3' below ground level and weld on ID plate. Erect marker and restore location.

15-055-20043-0000

SCHLUMBERGER**DUAL INDUCTION - LATEROLOG**

COUNTY FIELD OF LOCATION WELL COMPANY	COMPANY <u>TEXACO, INC</u>	
	WELL <u>GARDEN CITY 'B'-6</u>	
	FIELD <u>DAMME</u>	
	COUNTY <u>FINNEY</u>	STATE <u>KANSAS</u>
LOCATION <u>C-SE-SE</u>		Other Services: <u>FDC-GR</u>
Sec. <u>5</u> Twp. <u>22S</u> Rge. <u>33W</u>		
Permanent Datum: <u>GL</u> , Elev. <u>2886</u>		Elev.: K.B. <u>2899</u>
Log Measured From <u>KB</u> , <u>11</u> Ft. Above Perm. Datum		D.F. <u>2892</u>
Drilling Measured From <u>KB</u>		GL <u>2886</u>
Date	<u>9/10/71</u>	
Run No.	<u>ONE</u>	
Depth-Driller	<u>4800</u>	
Depth-Logger	<u>4792</u>	
Btm. Log Interval	<u>4786</u>	
Top Log Interval	<u>450</u>	
Casing-Driller	<u>9 5/8 @ 450</u>	@ @ @
Casing-Logger	<u>9.50</u>	
Bit Size	<u>8 3/4"</u>	
Type Fluid in Hole	<u>SM-S</u>	
Dens.	Visc. <u>9.2</u> <u>9.2</u>	
pH	Fluid Loss <u>6.8</u> <u>6.8</u> ml	ml ml ml
Source of Sample <u>CIRCULATED</u>		
R _m @ Meas. Temp.	<u>.93</u> @ <u>83°F</u>	@ °F @ °F @ °F
R _{ml} @ Meas. Temp.	<u>.292</u> @ <u>75°F</u>	@ °F @ °F @ °F
R _{mc} @ Meas. Temp.	<u>---</u> @ <u>---</u> °F	@ °F @ °F @ °F
Source: R _{ml} R _{mc}	<u>M</u> <u>---</u>	@ °F @ °F @ °F
R _{mc} @ BHT	<u>.32</u> @ <u>112°F</u>	@ °F @ °F @ °F
Time Since Circ.	<u>2 HOURS</u>	@ °F @ °F @ °F
Max. Rec. Temp.	<u>112</u> °F	@ °F @ °F @ °F
Equip. Location	<u>7568 LIBERAL</u>	
Recorded By	<u>PATTERSON</u>	
Witnessed By	<u>NORMAN</u>	

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1993
CONSERVATION DIVISION
Wichita, Kansas

The well name, location and borehole reference data were furnished by the customer.

FOLD HERE

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

October 20, 1993

Texaco E & P Inc
P O Box 2700
Pampa TX 79066-2700

Garden City "B" #6
API 15-055-20,043-0001
C SE SE
Sec. 05-22S-33W
Finney County

Dear J. M. Barnum,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760