

State of Kansas



15-083-30088-0600

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Wasinger of Quality Oil Co. has this

date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Quality Oil Co.

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name: Mooney "B" Well No. 1

Location: C NE SE Sec. 19 Twp. 22 Rge. 21 (E) (W)

County Hodgeman Total Depth 442' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

8 5/8" to 249' circulated w/ cement. 5 1/2" to 4437' cemented.

Top perforations 4360' Plug bottom w/ 20 sacks cement

Top of cement 4262' Mud. 4262' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 249'

Spotted 30 sacks cement 249' to 149' Mud 149' to 45'

Plug, Huls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent