

State of Kansas



15-083-30089-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Biggs of Pickrell Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company.

Complete Address: 705 Fourth Nat. Bank Bldg. Wichita, Kansas

Lease Name: Fall "A" Well No. 1

Location: C NE NE Sec. 21 Twp. 22 Rge. 21 (E) (W)

County Hodgeman Total Depth 4528' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Biggs was instructed to plug the well as follows:

8 5/8" to 304' circulated w/ cement. T.D. 4528'

Mud 4528' to 700' Spot 30 sacks cement 700' to 600'

Mud 600' to 350' Spot 35 sacks cement 350' to 250'

Mud 250' to 45' Plug, Halls & 15 sacks cement 45' to 0'

Weld plate On 8 5/8". Pump

Very truly yours,

Edgar J. Ewen
Conservation Division Agent