



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sullivan of Midwestern Supply has this

date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Midwestern Supply Co., Inc.

Complete Address: 710 Union National Bldg., Wichita, Kansas

Lease Name: Nichols Well No. 1-C

Location: C NE SW Sec. 25 Twp. 22 Rge. 21 (E) (W)

County: Hodgeman Total Depth 4541' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

8 5/8" to 401' circuited w/ cement. 4 1/2" to 4541' cemented.

Top perforations 4510' Plug bottom w/ sand & 4 sacks cement.

Top of cement 4350' Mud 4350' to 600'

Spot 80 sacks cement 600' to 300' Mud 300' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent