



15.093.10095-0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1977

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. R.C. Hallam of Cities Service Oil Co. has this

date requested permission to plug the following described well:

Mr. Hallam guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: 700 Sutton Pl. Bldg. 209 E. Williams, Wichita, KS

Lease Name: Barnett "A" Well No. 2

Location: 1980' FSL - 660' E.L. Sec. 6 Twp. 22 Rge. (E) (W) 22

County: Hodgeman Total Depth 4500' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hallam was instructed to plug the well as follows:

8 1/2" set to 249' 4 1/2" set to 4500'; Tubing
made of at 900' via hinge bridge. 1st plug
at 900' with 1 sh hull 2 fell + 20 shs - 50-50
Pos via 2 7/8 fell. 2nd plug at 600' with 2
fell, 1 hull + 30 shs 50-50. 3rd plug at 240'
with 30 shs 50-50.
4th plug at 60-0 with
10 shs.

Very truly yours,

Clarence Thomas
Conservation Division Agent