



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pulley of Mobil Oil Corp. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1070, Great Bend, Kansas

Lease Name: Salmans Well No. 1

Location: C SW SE Sec. 5 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4610' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 248' circulated w/ cement. 5 1/2" to 4609' cemented.

Top perforations 4523' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4450' Mud 4450' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 240'

Spot 30 sacks cement 240' to 140' Mud 140' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent