



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnson of Barbara Oil Co. has this

date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Barbara Oil Co.

Complete Address: 509 Union Center, Wichita, Kansas

Lease Name: Salmans Well No. 1

Location: NE SE Sec. 2 Twp. 22 Rge. 22 (S) (W)

County: Hodgeman Total Depth 4498' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

8 5/8" to 286' circulated w/ cement. Mud 4498' to 550'

Spot 35 sacks cement 550' to 450' Mud 450' to 280'

Spot 25 sacks cement 280' to 200' Mud 200' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent