



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Sage Drlg. has this
date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: W. L. Hartman

Complete Address: Box 54 Wichita, Ks.

Lease Name: Tucker Well No. 1

Location: SW NE Sec. 5 Twp. 22 Rge. (E)(W) 33

County: Finney Total Depth 4847' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Freeman was instructed to plug the well as follows:
Gum pits, circulate heavy mud, set cementing plug at 900' and displace
100 sk cmt thru drill pipe. Heavy mud to 420' set cementing plug and
displace 35 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 15 sk cmt to base of cellar.

Very truly yours,

Leo F. Messing
Conservation Division Agent