

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 24 1964

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Danny Biggs of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Swingle "B" Well No. # 3

Location: NW SE NW Sec. 22 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4385 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Biggs was instructed to plug the well as follows:

235' of 8 5/8" surface pipe, cemented with 205 sacks.  
Fill hole with mud to 260', 1st cementing plug, bridge with  
hulls, cement with 25 sacks. Fill hole with mud to 40', 2nd  
cementing plug, bridge with hulls, cement with 10 sacks to  
base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent