

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1963

CONSERVATION DIVISION  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

March 9, 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this

date requested permission to plug the following described well:

Mr. Percy Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth Nat'l. Bnk. Bldg. Wichita, Kansas.

Lease Name: Goenner #1 Well No. #1

Location: NW-SW-SE Sec. 27 Twp. 30S Rge. 9 (E) (W) X

County Kingman Total Depth 4457' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Percy Hall was instructed to plug the well as follows:

253' of 8 5/8" surface pipe circulated with 190 sacks cement.

Hole filled to 180' with heavy drill mud, 1/4 sack hulls, 1st

cementing plug and 20 sacks cement. Hole filled to 40' with

heavy drill mud, 1/4 sack hulls, 2nd cementing plug and 10 sacks

cement to base of cellar. Rathole bridged and 2 sacks cement.

Very truly yours,

*Herman Justus*  
Conservation Division Agent