

State of Kansas



15-083-20441-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

OCT 15 1975

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

CONSERVATION DIVISION Wichita, Kansas

Dear Sir:

Mr. Moore of C & G Drlg. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust

Complete Address: Box 187, Logan, Kansas

Lease Name: Ford Well No. 2

Location: NW SE Sec. 26 Twp. 22 Rge. (E)(W) 24

County: Hodgeman Total Depth 4660' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 550' thru drill

pipe. Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Conservation Division Agent (Signature)