

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County, Sec. 25 Twp. 22S Rge. (E)21 (W)

Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Nadel and Gussman
Lease Name Nichols Well No. 1
Office Address 1714 First Natl. Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 2, 19 70
Application for plugging filed (letter 4/6/70) April 2, 19 70
Application for plugging approved April 2, 19 70
Plugging commenced April 2, 19 70
Plugging completed April 2, 19 70
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves
Producing formation Depth to top Bottom Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	420	8-5/8"	420	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 600 feet. Set first plug @ 600 feet w/80 sacks cement.
Filled hole with heavy mud to 44 feet. Set second plug @ 44 feet w/10 sacks cement.
Filled rat hole w/3 sacks cement. Job complete @ 11:00 PM, April 2, 1970.

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. E. Hall*

830 Sutton Place - Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 6 day of April, 19 70



Barbara J. Layton
Barbara J. Layton Notary Public.

GABBERT-JONES, INC.
Wichita, Kansas
Drillers' Well Log

NICHOLS #1
C NE NW Section 25-22S-21W
Hodgeman County, Kansas

Commenced: March 23, 1970
Completed: April 2, 1970

OPERATOR - Nadel and Gussman

DEPTH		FORMATION	REMARKS
From	To		
0	60	Sand	
60	260	Shale	
260	422	Shale and red bed	Ran 13 joints 8-5/8" casing, set @ 420' w/260 sacks cement.
422	750	Shale and red bed	
750	764	Anhydrite	
764	850	Red bed	
850	975	Sand	
975	1406	Shale and red bed	
1406	1432	Anhydrite	
1432	2350	Shale and shells	
2350	4010	Shale and lime	
4010	4525	Lime	
4525	4530	Lime and chert	
4530	4540	Lime	
4540	4560	Lime and chert	
4560	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1970
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE NW Section 25-22S-21W, Hodgeman County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6 day of April, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

