


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County. Sec. 34 Twp. 22S Rge. 21 ~~XXX~~ (W)

Location as "NE/CNW%SW%" or footage from lines C NW NE
Lease Owner Herman Geo. Kaiser
Lease Name Draut Well No. 1
Office Address 909 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 20, 19 61
Application for plugging filed January 20, 19 61
Application for plugging approved January 20, 19 61
Plugging commenced January 20, 19 61
Plugging completed January 20, 19 61
Reason for abandonment of well or producing formation Dry Hole

-NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to 240 feet, set plug and cemented with hulls and 20 sacks cement through drill pipe. Mudded hole to 35 feet, set plug and cemented with hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1961
CONSERVATION DIVISION
Wichita, Kansas

1-27-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, contractor L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 61

My commission expires December 3, 1964. Herbert Hays Notary Public.

15-083-00122-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser**


SEC. **34 22S 21W**
LOC. **C NW NE R**

FARM **Draut** NO. **1**

TOTAL DEPTH **4,525'**
COMM. **1-4-61** COMP. **1-20-61**

COUNTY **Hodgeman**

SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED



CASING

20	10 ⁵ / ₈	260' cem. w/140 sx.
15	8 ⁵ / ₈	
12	6	
13	5	

ELEVATION
2266 GR.
2268 DF.
2271 KB.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	40
Shale & Shells	170
Sand	190
Shale & Shells	261
Shale, Shells & Red Bed	710
Red Bed	735
Anhydrite	755
Shale & Shells	845
Sand	965
Shale & Shells	1986
Shale & lime	2240
Lime	2425
Lime & Shale	2845
Shale & Lime	2965
Lime & Shale	3240
Shale & Lime	3550
Lime & Shale	3940
Lime	4210
Lime & Shale	4505
Cherty Lime & Shale	4525
Rotary T. D.	4525

Electric Log Tops

Anhydrite Top	735	+1533
Anhydrite Base	755	+1513
Heebner	3840	-1572
Toronto	3857	-1589
Douglas	3869	-1601
Lansing K.C.	3917	-1649
Base K. C.	4248	-1980
Marmaton	4255	-1987
Cherokee	4392	-2124
Mississippi	4494	-2226
Rotary T.D.	4525	-2257

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

By *L. G. Sponenberg*
L. G. Sponenberg

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 24th day of January, 1961.

Geraldine Hayes
Notary Public

My Commission Expires:

December 3, 1964.

RECEIVED
STATE COMMISSION
JAN 26 1961
CONSERVATION DIVISION
Wichita, Kansas