

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 6 TWP. 22S RGE. 22 N/W
Location as in quarters or footage from lines:
1980' FEL - 660' FSL

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Company
Lease Name Barnett "A" Well No. 3 SWD
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): SWD
Date Well Completed January 8, 1975
Application for plugging filed August 20, 1982
Plugging commenced September 28, 1982
Plugging completed October 25, 1982
Reason for abandonment of well or producing formation
No longer needed.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation Cedar Hills Depth to top 905' bottom 955' T.D. 1027'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	253'	- 0 -
				4 1/2"	1021'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pulled 28 joints of 2" VIP lined tubing. Cut off 4 1/2" and 8 5/8".
Welded steel cap on top. Pumped 100 sacks 50/50 pozmix, 4% gel, 3% CaCl-2
down top at 300 lbs. Plug and abandonment completed October 25, 1982.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Sedgwick, ss.
W. J. Devaney (employee of owner) or ~~(owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-27-85

(Signature) [Signature] W. J. Devaney
800 Sutton Place, 209 East William
Wichita, Kansas (Address) 67202

SUBSCRIBED AND SWORN TO before me this 1 day of November, 19 82
STATE CORPORATION COMMISSION
[Signature]
Notary Public.

My Commission expires: 2-27-85

NOV 3 1982
CONSERVATION DIVISION
Wichita, Kansas 11-3-82

DRILLERS LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

BARNETT NO. 3
C SW SE Sec. 6-22S-22W
Hodgeman County, Kansas

Total Depth: 4555'

Elevation 2295 K.B.
Production: Dry

Commenced: 6/20/62 Completed: 7/4/62

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" surface pipe at 253' with 175 sacks cement.

Figures indicate bottom of formations:

TOPS

Post Rock	50'	Heebner	3855 (-1560)
Shale	515'	Lansing	3934 (-1630)
Shale & Sand	843'	Base Kansas City	4246 (-1951)
Anhydrite	856'	Cherokee Shale	4430 (-2135)
Shale & Red Bed	1470'	Mississippi (Osage)	4544 (-2249)
Shale & Shells	1870'	Rotary Total Depth	4555 (-2260)
Shale & Lime	2230'		
Lime	2810		
Lime & Shale	3932'		
Lime	4228'		
Lime & Shale	4238'		
Lime	4470'		
Lime & Chert	4546'		
Lime	4555'		

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1962
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

RECEIVED
STATE CORPORATION COMMISSION

IMPERIAL OIL COMPANY

AUG 17 1962

CONSERVATION DIVISION
Wichita, Kansas

BY Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 16th day of July, 1962.

My commission expires:

July 5, 1966

Bette J. Silcott
Bette J. Silcott, Notary Public