


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 6 Twp. 22 Rge. 22 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name Barnett Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/31 19 57
Application for plugging filed 7/31 verbally 19 57
Application for plugging approved 7/31 verbally 19 57
Plugging commenced 7/31 19 57
Plugging completed 7/31 19 57
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4651 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole within 250' of top. Put in 1/2 sx hulls, plug down to 250', put 20 sx of LeHigh cement in, fill hole 35' from groundlevel, 1/2 sx, push plug down 35', 1 sx cement on top of plug. Finish plugging hole w/9 sacks cement to top of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of ~~drilling~~ Contractor Bennett & Roberts Drilling Co.
Address Russell, Ks.

STATE OF KANSAS COUNTY OF RUSSELL ss.
Harold Wurst (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of August, 19 57

My commission expires 6/17/58

Clara Hummel 8-5-57
Notary Public

PLUGGING
FILE SEC. 6 T. 22 R. 22W
BOOK PAGE 33 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1957
CONSERVATION DIVISION
Wichita, Kansas

15-083.0015.0000

Bennett & Roberts Drilling Co.
Barnett #1

SE SE SW Sec. 6-22-22W
Hodgeman County, Kans.

R.T.D. 4651

Commenced 7/10/57
Completed 7/31/57

8 5/8" Set @ 253' with 200' ex

Surf. soil & post rock	50'
Clay, Shale & Shells	130
Sand	140
Blue Shale	170
Gray Shale	240
Blue Shale & Shells	253
Shale & Clay	660
Red Rock & Sand	830
Red Bed & Sand	920
Sand	1125
Shale & Sand, Shells	1425
Shale & Shells	1470
Thin streaks Anhydrite	1480
Shale & Shells	1670
Shale, Shells, Red Rock	1900
Shale & Shells	2275
Shale & Lime	3470
Shale & Shells	3520
Shale & Lime	3577
Shale & Lime Streaks	3681
Lime	3725
Lime & Shale	3894
Lime	4445
Lime & Shale	4487
Lime	4512
Cherty Lime	4530
Cherty Conglomerate	4545
Cherty Lime	4551
Mississ. & Cherty	4573
Cherty Lime	4592
Lime & Chert	4620
Cherty Lime	4651

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By John B. Turner

Subscribed and sworn to before me this 2nd day of August, 1957.

Clara Hummel
Notary Public

My Commission Expires 6/17/58

PLUGGING
SEC. 6 T. 22 R. 22W
BOOK PAGE 33 LINE 4

RECEIVED
STATE CORPORATE COMMISSION
AUG 5 1957
CONSERVATION DIVISION