

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County, Sec. 2 Twp. 22 Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines NE-SE

Lease Owner Barbara Oil Company

Lease Name Salmans Well No. 1

Office Address 509 Union Center Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 19 19 70

Application for plugging filed March 20 19 70

Application for plugging approved March 19 19 70


Plugging commenced March 19 19 70

Plugging completed March 20 19 70

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4498 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Shale		0	240	8 5/8	289'	None
Shale		240	289			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up with heavy mud to 550 feet. Cement (35 sx.) from 550 feet to 430 feet. Mud to 280 feet. Cement (25 sx.) from 280' to 200'. Mud & hulls to 40 feet. Halliburton cement plug then cement (10 sx.) to cellar. Put 2 sx. in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. Douglas Myers (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Douglas Myers  
509 Union Center Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of March, 19 70

My commission expires August 12, 1971

Doris Oglesbee  
Doris Oglesbee  
Notary Public.



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1970  
CONSERVATION DIVISION  
Wichita, Kansas

SALMAN #1  
C NE SE Section 2-22S-22W  
Hodgeman County, Kansas

Commenced: March 9, 1970  
Completed: March 20, 1970

OPERATOR - Barbara Oil Company

DEPTH		FORMATION	REMARKS
From	To		
0	240	Clay and shale	
240	289	Shale	Ran 8 joints 8-5/8" casing, set @ 289' w/200 sacks cement.
289	790	Shale	
790	985	Sand	
985	1355	Shale and red bed	
1355	1390	Anhydrite	
1390	1710	Shale and shells	
1710	2245	Shale and lime	
2245	2760	Lime	
2760	3867	Lime and shale	
3867	4460	Lime	
4460	4498	Lime and chert	
4498	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SE Section 2-22S-22W, Hodgeman County, Kansas, to the best of my knowledge and belief.

*E. E. Hall*  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 23 day of March, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

*Barbara J. Layton*  
Barbara J. Layton, Notary Public

