

15-055-00272-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER Completed 12-24-58

COUNTY Finney
Garden City Gas Co.
LEASE NAME Unit WELL# 1

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

SPOT LOCATION C NW

LEASE OPERATOR Texaco Inc.

SEC. 5 TWP. 22 RGE. 33 (E) OR (W)

PHONE # (918) 743-5311

OPERATORS LICENSE NO. 5153

CHARACTER OF WELL Gas (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 12-24-58 PLUGGING COMMENCED 6-8-83

PLUGGING COMPLETED 6-8-83 REASON FOR ABANDONMENT OF WELL OR PRODUCING
FORMATION Uneconomical

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Garden City, KS - Steve Duran

IS ACO-1 FILED? No IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION Harrington DEPTH TO TOP 2528'
Krider DEPTH TO TOP 2544' BOTTOM T.D. 2600

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	326'	-----
				5-1/2"	2584'	-----

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Well was plugged as follows:
From 2556-2000' w/50 sx cmt; from 2000-490' w/8 sx gel; from
490-4' w/54 sx cmt; from 4'-GL w/Dirt

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)


NAME OF PLUGGING CONTRACTOR Sargents Casing Pulling LICENSE No. 6547
ADDRESS P.O. Box 506, Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Tulsa, ss.

B. A. Batson (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT. SO HELP ME GOD.

(SIGNATURE) B. A. Batson
Texaco Inc.
(ADDRESS) P.O. Box 2420, Tulsa, OK

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8th DAY OF July, 1983



RECEIVED
STATE CORPORATION COMMISSION NOTARY PUBLIC
Eloise Brannon

MY COMMISSION EXPIRES: January 25, 1987

JUL 13 1983
CONSERVATION DIVISION
Wichita, Kansas

7-13-83

FORM CP-4
REVISED 06-83

WELL LOG

COMPANY THE TEXAS COMPANY
FARM GARDEN CITY COMPANY NO. 1


SEC. 5 T. 22S R. 33W
LOC. C/NW/4

DEPTH 2585'

COUNTY FINNEY CO., KANSAS

COMM. December 20, 1958 COMP. December 24, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 9 5/8" @ 326' W/350 sax.
5 1/2" @ 2584' W/650 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

75	Surface soil & shale
326	Shale & sand
1450	Shale
1650	Sand
2325	Shale
2585	Shale & lime
2585	T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1963

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 GARDEN CITY COMPANY

Verne A. Morris

Subscribed and sworn to before me this 2nd day of January 19 59

My Commission Expires: NOVEMBER 12, 1962

[Signature]
NOTARY PUBLIC

WELL LOG

15.055-00272-0000

COMPANY THE TEXAS COMPANY

SEC. 5 T. 22S R. 33W

FARM GARDEN CITY COMPANY NO. 1


LOC. C/NW/4

TOTAL DEPTH 2585'

COUNTY FINNEY CO., KANSAS

COMM. December 20, 1958 COMP. December 24, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 9 5/8" @ 326' W/350 sax.
5 1/2" @ 2584' W/650 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

75	Surface soil & shale
326	Shale & sand
1450	Shale
1650	Sand
2325	Shale
2585	Shale & lime
2585	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1963

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 GARDEN CITY COMPANY

Subscribed and sworn to before me this 2nd day of January 19 59

My Commission Expires: NOVEMBER 12, 1962

Verne A. Morris

[Signature]
NOTARY PUBLIC