

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20043-0001

LEASE NAME Garden City "B"

WELL NUMBER 6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 22S RGE. 33 (R) or (W)

COUNTY Finney

Date Well Completed 9-21-71

Plugging Commenced 11-19-93

Plugging Completed 11-22-93

LEASE OPERATOR Texaco E & P Inc.

ADDRESS P.O. Box 2700, Pampa, TX 79066-2700

PHONE# (806) 665-1876 OPERATORS LICENSE NO. 4742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-22-93 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Log sent W/CP-1

Producing Formation St. Genevieve Depth to Top 4638' Bottom 4644' T.D. 4800'
St. Louis

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
St. Genevieve	Oil/Water	Surf.	449	9-5/8"	449'	None
St. Louis	Oil/Water	Surf.	4799	7"	4799'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

(See back)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Energy Services License No. 5287

Address P.O. Box 1598, Liberal, KS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco E & P Inc.

STATE OF Texas COUNTY OF Gray, ss.

Texaco E & P Inc. - J.M. Barnum


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct, so help me God.

(Signature) J.M. Barnum

(Address) (as above)

RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
DEC 17 1993

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1993



Merle W. Terrell
Notary Public

Plugging Method

1-25-93 - Set 7" CIBP @ 4588' w/2' sx cement on top of plug to 4579'. (calc).
11-22-93 - Ran 2-3/8" tbg. to PBTD & circ. hole full of 9# mud. HLS
perforated 7" csg. w/4 shots @ 1100'. Pumped 227 sx 60/40 poz cement w/8%
gel down 7" csg. @ 2 BPM and 750#. Cement did not circ. to surface on
backside. Left 7" csg. full of cement to 4' below G.L. Pumped 41 sx 60/40
poz cement w/8% gel down backside @ 500#. Cut off csg. 4' below G.L. &
capped well.

