


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County, Sec. 22 Twp. 30S Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Pickrell Drilling Company
Lease Name Swingle F Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 27 19 61
Application for plugging filed October 27 19 61
Application for plugging approved October 27 19 61
Plugging commenced October 27 19 61
Plugging completed October 27 19 61
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation Depth to top Bottom Total Depth of Well 4375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'. Set Plug. Cemented with 20 sacks cement. Heavy mud to 40'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat holde with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1961
CONSERVATION DIVISION
Wichita
10-31-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gerald W. Pike (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald W. Pike
Gerald W. Pike
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 61

Maxine Johnson
Maxine Johnson Notary Public.

My commission expires September 24, 1962

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

Rotary Drilling Commenced 10/15/61

Rotary Drilling Completed 10/27/61

LOCATION: SWINGLE F #1 - C NE SE, Sec. 22-30S-9W,
Kingman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 250' (7 jts.) 8 5/8" 20# Surface Casing with 165 sacks cement.
Circulated. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

65'	Sand	<u>Circulated for Samples</u>	
254'	Red Rock	4277'	
660'	Red Rock & Shale	4375'	
1380'	Shale, Shells & Lime	<u>Slope Test</u>	
1650'	Lime & Shale	1380'	0°
2080'	Lime	2415'	0°
3145'	Lime & Shale	3145'	0°
3305'	Lime; Shale & Sand	4220'	0°
3465'	Lime & Shale		
3584'	Lime, Shale & Sand	<u>S. L. M.</u>	
4055'	Lime	1500'	
4316'	Lime & Shale	2500'	
4375'	Mississippi R.T.D.	3800'	

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1961
CONSERVATION DIVISION
Wichita Kansas

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By Gerald W. Pike
Gerald W. Pike Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 20th day of October, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Maxine Johnson Notary Public