

15-095-1000(-0000)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # Comp. 12-12-59 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003  
(owner/company name) (operator's)

ADDRESS 3017 N. Cypress CITY Wichita

STATE Kansas ZIP CODE 67226-4003 CONTACT PHONE # (316) 636-2737

LEASE Messenger "L" WELL# 3 SEC. 12 T. 30S R. 9W (East/West)

SE - SW - SE - SPOT LOCATION/QQQQ COUNTY Kingman

       FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

       FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#       

CONDUCTOR CASING SIZE        SET AT        CEMENTED WITH        SACKS

SURFACE CASING SIZE 8-5/8" SET AT 261' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4337' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs @ 4246-4274'

ELEVATION 1601 GL T.D. 4338' PBDT 4317' ANHYDRITE DEPTH         
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4200' & cap with 5 sx cement. Shoot & pull casing according to stretch. Pull casing to 1350' & spot 35 sx cement. Pull casing to 850' & spot 35 sx cement. Pull casing to 310' & circulate cement to surface. Pull remaining casing & top off cement. 60/40 Poz 4% Gel. Orders by Steve VanGieson w/ KCC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?

If not explain why?       

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl J. Hanson PHONE# (316) 272-1296

ADDRESS P. O. Box 2250 City/State Garden City, KS 67846

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30346  
(company name) (contractor's)

ADDRESS P. O. Box 781624 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)       

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-17-94 AUTHORIZED OPERATOR/AGENT:       

RECEIVED  
NOV 18 1994  
3/95  
Signature:         
(signature)

2)



## Kansas Corporation Commission

Joan Finney, Governor   Susan M. Seltsam, Chair   F.S. Jack Alexander, Commissioner   Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director   Brian Moline, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

November 21, 1994

McCoy Petroleum Corporation  
3017 N Cypress  
Wichita KS 67226-4003

Messenger "L" #3  
API 15-N/A  
SE SW SE  
Sec. 12-30S-09W  
Kingman County

Dear Daryl J. Hanson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

District: #2  
202 W. First, Suite 304  
Wichita KS 67202  
(316) 263-8809