

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-19013-0001

SE, Sec. 6, T 22 S, R 22 W/E

660' feet from N/S section line

1980' feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Barnett A Well # 3

Operator: Cities Service Co.
Name & Address 209 E William
800 Sutton Pl
Wichita Mo. 67202

County Hodgeman

Well Total Depth 1027 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Cities Service Co. License Number 5447

Address SAME

Company to plug at: Hour: 11:00 AM Day: 25 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Bob Wulfer

(company name) Cities (phone)

were: 4 1/2" @ 1021' w/ cement cur.

Packer in hole @ 878'

plug fill 4 1/2" from T.O. to surface with cement

Signed Steve Stewart
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 AM Day: 25 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT

Filled 4 1/2" casing with 100 sx cement + 2 sx
balls

Max pressure 300 #

Shut in 300 #

Remarks: Cement by Halliburton

STATE CORPORATION COMMISSION
RECEIVED
NOV 2 1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Steve Stewart
(TECHNICIAN)

INVOICED

DATE 11-5-82

INV. NO. 1483-W

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

BARNETT NO. 4
C NE NW Sec. 6-22S-22W
Hodgeman County, Kansas

Total Depth: 4542'

Elevation: 2255 K.B.
Production: Dry

Commenced: 12/18/62 Completed 1/1/63

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: set 8-5/8" surface pipe at 243' with 200 sacks.

Figures indicate bottom of formations:

Tops

| | | | |
|-----------------|-------|--------------------|--------------|
| Shale & Sand | 200' | Anhydrite | 1421 (-834) |
| Shale & Shells | 243' | Heebner | 3810 (-1555) |
| Shale & Sand | 794' | Toronto | 3825 (-1570) |
| False Anhydrite | 807' | Douglas Lime | 3866 (-1611) |
| Shale & Sand | 1422' | Lansing | 3888 (-1633) |
| Anhydrite | 1510' | B/Kansas City | 4203 (-1948) |
| Shale & Shells | 2155' | Cherokee Shale | 4380 (-2125) |
| Shale & Lime | 3915' | Conglomerate | 4448 (-2193) |
| Lime | 4500' | Mississippian | |
| Lime & Chert | 4535' | (Warsaw) | 4494 (-2239) |
| Chert | 4542' | Mississippian | |
| | | (Osage) | 4517 (-2262) |
| | | Rotary Total Depth | 4542' |

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling report.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1963

CONSERVATION DIVISION
Wichita, Kansas

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh
Raymond R. Dombaugh

Subscribed and sworn to before me this 17th day of January, 1963.

My commission expires:

July 5, 1966

Bette J. Silcott
Bette J. Silcott,
Notary Public