

To: 1 051409
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 055-20,038 -0000

C NW SW, SEC. 5, T. 22 S, R. 33 W/E

1980 feet from S section line

4620 feet from E section line

Lease Name Garden City "B" Well # 2

County Finney 156.00

Well Total Depth 4800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 417

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 27 Month: 2 Year: 19 91

Plugging proposal received from Doug

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4799' w/200 sx cement, Perfs at 4332-36, 4391-95, 4415-22, 4719-34'

Packer left in hole at 4528'

1st plug pump 35 sx cement on top of packer,

2nd plug at 1100' with 50 sx cement,

3rd plug at 670', circulate cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:10 p.m. Day: 28 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement to 4200', (common cement),

2nd plug shot the pipe at 1100' and displaced 50 sx cement down 5 1/2" to 1000' (common cement),

3rd plug shot the pipe at 668' and pumped down 5 1/2" and circulated up 8 5/8" X 5 1/2"

annulus with 65/35 Pozmix. (200 sx).

Remarks: Used common cement and 65/35 Pozmix by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

DATE 3-12-91

MAR - 6-1991

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 31115

CONSERVATION DIVISION
Wichita, Kansas

3-6-91

FORM CP-2/3
Rev. 01-84