

To: 1 051544 4-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,058-0001

2021

C SW SE, SEC. 5, T. 22 S, R. 33 W EX

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Garden City B Well # 7

Operator: Texaco E&P Inc.

County Finney

Name:

Address P.O. Box 2700

Well Total Depth 4800 156.00 feet

Pampa, TX 79066-2700

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 410

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Bruce Well Service License Number 7407

Address P.O. Box 1597, Liberal, KS 67905-1597

Company to plug at: Hour: 9 a.m. Day: 21 Month: 4 Year: 19 92

Plugging proposal received from John Robertson

(company name) Texaco (phone) 806-665-1876

were: 7" at 4799' w/100 sx cement, PBTD 4766', 4752-4326' (5 sets) Squeezed at 3940-4010'

1st plug set CIBP at 4250' with 2 sx cement on top.

2nd plug squeeze with 80 sx cement at 1200',

3rd plug spot 50 sx cement from 440-175',

4th plug spot 10 sx cement from 40-0', 5th plug pump 80 sx down annulus.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 5 p.m. Day: 21 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3959',

2nd plug ran tubing to 3950', loaded hole with mud and spotted 10 sx cement at 3950',

3rd plug perforated at 1200', set a retainer at 1157' and spotted 65 sx cement through

the retainer and 5 sx cement on top,

4th plug pulled tubing to 440' and circulated cement to surface,

5th plug pumped 80 sx cement down 9 5/8" X 7" annulus. Maximum pressure 200 psi and shut in 200

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (dd) (NAME) observe this plugging.

Signed Richard W. Lacy  
(TECHNICIAN)

DATE 5-5-92

INV. NO. 35154

FORM CP-2/3