

To: 1 080127 5-29  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 055-20,081-0001  
C SW NW, SEC. 5, T 22 S, R 33  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 31658

Lease Name Garden City B Well # 10  
County Finney 156.00

Operator: Cross Timbers Operating Co.  
Name & Address 210 Park Ave., Ste. 2350  
Oklahoma City, OK 73102

Well Total Depth 4800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Petrofield Services Corp. License Number 31330  
Address 110 S. Hartford, #330, Tulsa, OK

Company to plug at: Hour: 1 P.M. Day: 27 Month: 5 Year: 19 97

Plugging proposal received from Lonnie Tarvin  
(company name) Cross Timbers (phone) 806-435-2061

Work: 5 1/2" at 4799' w/200 sx cement, PBTD 4765', Perfs at 4325-30, 4385-87, 4406-12, 4703-11'  
DV tool at 2810' w/100 sx cement, Had casing leak squeezed at 3470-3502' w/150 sx cement  
1st plug set CIBP at 4397', 2nd plug set CIBP at 4275', 3rd plug at 2000' with 50 sx cement,  
4th plug at 1150' with 80 sx cement, 5th plug at 450' with 50 sx cement,  
6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_  
Operations Completed: Hour: 1 P.M. Day: 29 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4397' with 2 sx cement,  
2nd plug set CIBP at 4275' with 2 sx cement, Shot casing at 1150', not free,  
3rd plug pumped 80 sx cement to 1150', shot casing at 700', pulled casing.  
4th plug ran tubing to 450' and pumped 50 sx cement,  
5th plug pulled up to 40' and pumped 25 sx cement.

RECEIVED  
TRANSAS CORP COMM  
1-2-97  
JUN - 2 A 3 38

Remarks: Used Class A cement by Petrofield Services Corp. Recovered 700' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (and ~~my~~ observe this plugging.

Signed Kevin D. Streets (TECHNICIAN)

INVOICED  
DATE JUN 05 1997  
INV. NO. 48226  
5-29