

2 040517

11-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 15-095-20,865-0000

C NE SW SEC. 24, T 30 S, R 9W (W)E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3517

Lease Name Swingle Well # 1

Operator: Columbian Services Corp

County Kingman 138.78

Name & Address P.O. Box 3501

Well Total Depth 4270 feet

Topeka, KS 66601-3501

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 256

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number \_\_\_\_\_

Address Chase, KS

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Stan Brady

(company name) Columbian Services (phone) \_\_\_\_\_

were: 4-1/2" 4269' - perf. 4255-4260'

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:00 Day: 17 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT The perfs were covered w/sand and capped w/4 sx cmt to 4200' - 4-1/2" was shot loose and pulled to 1500' where a 35 sx plug cmt was spotted - 4-1/2" was pulled to 1100' where 35 sx plug cmt was spotted - 4-1/2" casing was pulled to 300' & cmt circ to surface.

RECEIVED STATE CORPORATION COMMISSION

Allied #6185 60/40 2% gel

DEC 19 1989 12-19-89

Remarks: (If additional description is necessary, use BACK of FORM CP-2/3)

CONSERVATION DIVISION

INVOICED

DATE 1-3-1990

Signed [Signature] (TECHNICIAN)

INV. NO. 26855