

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21751-00-00
Spot: SWSENW Sec/Twnshp/Rge: 22-27S-14W
3084 feet from S Section Line, 3748 feet from E Section Line
Lease Name: REED C Well #: 1
County: PRATT Total Vertical Depth: 4680 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		WITH 2 SX CMT
PROD	4.5	4679	2050	WITH 200 SX CMT
SURF	8.625	373		WITH 235 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2016 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3900' WITH 2 SX CMT. PRESSURE TEST CASING. PLUG AT 970' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2016 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3900' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PRESSURE TEST 4 1/2" CASING TO 275#. HELD. 1ST PLUG AT 960' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. 11/17/16: TOP OFF WELL WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4069	4073		
3948	3952		
3944	3946		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. CONTROL # 20170017

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
NOV 22 2016
KCC DODGE CITY

KCC WICHITA
DEC 05 2016
RECEIVED