

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

6-30-75

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drlg Co

Complete Address 705 4th Natl Bldg Wichita, KS

Lease Name Swingle E Well No. 1

Location NE/SE/NE Sec. 21 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4391

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co Inc

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 3:00 PM Day 28 Month 6 Year 1975

The above well was plugged as follows:

240 ft 8 5/8 surface cement circulated. 4390 ft 5 1/2 long string
cemented with 90 sacks. Top perf. 4298 ft. Sand to 4250 ft, 5 sacks
cement with bailer. Pulled 3400 ft 5 1/2. Set 10 ft rock bridge at
200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed Russell B. Schuster
Well Plugging Supervisor

INVOICED

DATE 7/31/75
INV. NO. 1561-W