

15-009-05584-0000
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 68-31

LOCATION SE-SF-SW

SEC. 26 TWP. 16 RGE. 11-ew

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Kraft "A"

Operator The Eldorado Refining Co. Address Box #551 Eldorado Kans.

Field _____ County Barton

Total Depth 3400 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 316 ft. Circulated with cement.
5 1/2" casing set at 3387 ft. - 50 sacks of cement.
Plugged back with sand to 3375 ft. - Run back
5 sacks of cement at 3375 ft. - Ripped off & hulled the
5 1/2" casing - mud to 300 ft. - Set rock bridge &
20 sacks of cement at 300 ft. - mud to 35 ft. - Plug
& 10 sacks of cement at the surface -
Shull Casing Pulling Co. Plugging Contractors

PLUGGING
FILE SEC. 26 TWP. 16 R. 11
BOOK PAGE 68 LINE 31

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1953
01-23-53
CONSERVATION DIVISION
Wichita, Kansas

C. D. Strush
District Conservation Agent
Date 1-21-53