



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 19 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Rody of Rains has this

date requested permission to plug the following described well:

Mr. Rody guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Ct., Wichita, Kansas

Lease Name: Sheppard Well No. 1

Location: C NE SE Sec. 25 Twp. 22 Rge. 25 ~~(E)~~ (W)

County: Hodgeman Total Depth 4700' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Rody was instructed to plug the well as follows:


8 5/8" to 370' circulated w/ cement. Mud 4700' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 350'

Spot 30 sacks cement 350' to 250' Mud 250' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent