

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-083-30005-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1965
3-23-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clem Burton of Pickrell ~~Pickrell~~ Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell ~~Pickrell~~ Drilling Co.

Complete Address: 705 4th Natl. Bk. Bldg. Wichita, Kansas

Lease Name: Kellogg Well No. # 1

Location: C SW NE Sec. 23 Twp. 22S Rge. 25 NE (W)

County Hodgeman Total Depth 4698' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

8 5/8" - 227' Circulated w/cement.

Mud 4698' to 700' Spotted 25 Sax. cement 700' to 625'

Mud 625' to 230' Spotted 25 Sax. cement 230' to 155'

Mud 155' to 45' Plug, Halls, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
Conservation Division Agent