



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Oglesbee of Kewanee has this

date requested permission to plug the following described well:

Mr. Oglesbee guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Co.

Complete Address: Box 2093; Wichita, Kansas

Lease Name: Red Well No. 1

Location: C NE NW NE Sec. 22 Twp. 22 Rge. 25 (E)(W)

County: Hodgeman Total Depth 4703' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Oglesbee was instructed to plug the well as follows:

8 5/8" to 551' cirul ted w/ cement. 5 1/2" to 4690' cemented.

Top perforations 4604' Plug bottom w, sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spot 35 sacks cement 800' to 700' Mud 700' to 500'

Spot 35 sacks cement 500' to 400' Mud 400' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent