



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Pulley of Rockhold Engineering, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Petroleum Inc.

Complete Address: 800 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Kansas 67202

Lease Name: Westerman "C" Well No. 1

Location: SE NE SE Sec. 19 Twp. 30 Rge. 9W (E) (W)

County: Kingman Total Depth: 4445'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Pulley was instructed to plug the well as follows:

280' of 8 5/8" SP W/225 sks

5 1/2" set @ 4444' W/100 sks Plug back to 4400'

Top Perf 4402-4406 Sand Back to 4350' & W/5 sks

Pumped 15 gel-6 hulls- 10 gel, released plug and displaced W/150 sks common

cement 2% gel 3% C.C. Cemented by Sun

Recovered-2800' of 5 1/2" csg. SIP-300#

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION
1-19-82
JAN 19 1982

[Signature]
Conservation Division Agent
CONSERVATION DIVISION
Wichita Kansas