

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Dale Robinson of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Robinson guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Lattimore Well No. "B" #1

Location: C NW SE Sec. 20 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4429 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Robinson was instructed to plug the well as follows:

228' of 8 5/8" surface pipe, cement circulated with 175  
sacks. Fill hole with mud to 240', 1st cementing plug,  
1/2 sack hulls, cement with 20 sacks. Fill hole with mud  
to 40', 2nd cementing plug, 1/2 sacks hulls, cement with  
10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent