



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 17 1970
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: E. H. Wood, Jr.

Complete Address: 102 E Insurance Bldg. Wichita, Ks

Lease Name: Lattimore Well No. 1

Location: NE/NE/SE Sec. 20 Twp. 30s Rge. 9 (E)(W) W

County: Kingman Total Depth 4370 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

250 ft of 8 5/8 surface pipe cemented with 200 sacks. Fill
hole to 225 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

J. Russell Bherstein
 Conservation Division Agent