


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Finney

County. Sec. 22 Twp. 22S Rge. (E) 31 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE-NW-NW

Lease Owner The Carter Oil Company

Lease Name Vashti Russell Well No. 1

Office Address Box 786 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-19-53 19

Application for plugging filed 1-20-53 19

Application for plugging approved 1-20-53 19

Plugging commenced 1-21-53 19

Plugging completed 1-22-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Murrie A. Reives

Producing formation None Depth to top Bottom Total Depth of Well 4850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Winfield			2743'	10 3/4"	338'	0
Cherokee			4720'			
Mississippi			4743'			
St. Louis			4773'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud 4850' to 351'
Cement 351' to 300'
Mud 300' to 30'
Cement 30' to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1953
CONSERVATION DIVISION
Wichita

2-28-53

Name of Plugging Contractor The Rine Drilling Company
Address 320 Central Bldg.
Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. A. Reives* (Dist. Supt.)

Box 786 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27 day of Feb, 1953

My Commission Expires July 29, 1954

My commission expires

RECEIVED 23-8390-s 6-51-20M
STATE CORPORATION COMMISSION

FEB 23 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FEB 22 1953
BOOK PAGE 74 LINE 39

State

15-055-10109-0000

The Carter Oil Company
RUSSELL #1

NE-12W-NW,
Sec. 22-22s-31W
FINNEY COUNTY, KANSAS

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
STARTED: 12-29-52 FINISHED: 1-23-53

LOG

CLAY & ROCK	0	-	50	
SAND	50	-	200	
SHALE & SHELLS	200	-	400	10-3/4" CSG. @ 338' w/300 sx AND 200' C.C.
CEMENT	330	-	351	
SHALE	400	-	1250	EC @ 600' - 1°
RED BED	1250	-	1505	EC @ 1000' - 3/4°
ANHYDRITE	1505	-	1550	EC @ 1500' - 0°
SHALE	1550	-	1880	
RED BED - SHALE - SHELLS	1880	-	2115	EC @ 2000' - 3/4°
LIME - SHALE	2115	-	2655	EC @ 2600' - 15°
LIME	2655	-	2810	
LIME - SHALE	2810	-	3810	EC @ 2900' - 3/4°
LIME	3810	-	4055	EC @ 3130' - 10°
LIME - SHALE	4055	-	4125	EC @ 3600' - 3/4°
LIME	4125	-	4565	EC @ 4180' - 10°
LIME & SHALE	4565	-	4595	EC @ 4560' - 10°
LIME	4595	-	4850	RKB-TD D & A PLUGGED W/HEAVY MUD TO 350' WOODEN PLUG & 25 SX CEMENT. @ 350' HEAVY MUD TO 30' WOOD PLUG & 10 SX CEMENT TO CELLAR.

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE
RUSSEL WELL NO. 1, LOCATED NE-NW-NW, SEC. 22-22s-31W, FINNEY COUNTY, KANSAS.

R. M. Green
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 27th DAY OF JANUARY, 1953.

Leonard Pederson
NOTARY PUBLIC

MY COMMISSION EXPIRES APRIL 20, 1955.

PLUGGING
FILE SEC 22T 22 R 31W
BOOK PAGE 24 LINE 29